

<b>Mercy Corps - Gadarif State Office</b>	
<b>STABLE Project BHA</b>	<b>Project No:33602</b>
<b>Bills of Quantities for Hand wash facility (For One Unit)</b>	
<b>Project name:</b>	mobile Hand wash facility for 3 schools in Alfaw Locality (12Units)
<b>Project Location:</b>	village 4 / Alfaw Locality
<b>GPS:</b>	N 13° 520' .09" E 34° 12' 15.3"

Item	Description	Unit	Quantity	Unit Rate	Total amount
<b>1</b>	<b>Hand wash facilities:</b>				
1.1	Supply & erect 250 L capacity, plastic cylindrical storage water tank (Tiga), mounted on a 0.8 meters high steel tower with two steel sinks plus two 1/2 inch taps (one in each side) and connect to 20 liters waste water container under the sinks based on design. connect the waste water container with 5 meters hose away from mobile handwash facility. The price is include of all necessary fittings, valves, connection and piping, all according to technical specifications and the directions of the Engineer.	pcs	1		
1.2	<b>Steel tower for water tank</b>				
	Supply, install and welding a square water tank tower width 0.9 x 0.9x 0.8 meters dimension made of Steel angle 2"x 2" with according to drawings, specifications and the directions of the Engineer. Plus one coat antirust and three coats of oil paint,	pcs	1		
	<b>The cost in SDG for one mobile handwash</b>				
	<b>Overhead 30 %</b>				
	<b>Total cost in SDG for one unit</b>				
	<b>Total USD</b>				
	<b>Total cost for 12 mobile hand washing in SDG</b>				
	<b>Total cost in USD for 12 units</b>				