Mercy Corps - Gadarif State Office STABLE Project BHA Project No:33602 Bills of Quantities for Mobile Hand wash facility (For One Unit) Project name: hand wash facility for Market (4 Units) Project Location: Barbar Area - Alguraisha Locality - Gedaref State GPS N 13° 38' 26.412" E 36° 08' 10.32"

Item	Description	Unit	Quantity	Unit Rate	Total amount
1	Hand wash facilities:				
1.1	Supply & erect 250 L capacity, plastic cylindrical				
	storage water tank (Tiga),mounted on a 0.8				
	meters high steel tower with two steel sinks				
	plus two 1/2 inch taps (one in each side) and				
	connect to 20 lietters waste water container				
	under the sinks based on design. connect the	pcs	1		
	waster water contianer with 5 metters hose	pes	_		
	away from mobile handwash ficility. The price is				
	include of all necessary fittings, valves,				
	connection and piping, all according to technical				
	specifications and the directions of the Engineer.				
1.2	Steel tower for water tank				
	Supply, install and welding a square water tank		1		
	tower width 0.9 x 0.9x 0.8 meters dimention				
	made of Steel angle 2"x 2" with according to	pcs			
	drawings, specifications and the directions of the				
	Engineer. Plus one coat antirust and three coats				
	of oil paint,				
	The cost for one mobile handwash facility				
	Overhead 30 %				
	Total in SDG				
	Total in USD				
	Total cost in SDG for 4 units				
	Total USD for 4 units				