

**BOQ for construction VIP latrines(with two drops hall) in Souni& Alfajer Ajadeed School**

SN	Item Description	unit	Quantity	Unit Price (SDG)	Total Price (SDG)
9	Provide & casting reinforce concrete beam section 20*20 cm mix 1:2:4, concrete beam will be Joining with external wall 6m*2.4m,4T12mm,c/c steel bars will be used as well, 4times/day/4days watering will be used.	M.L	33.5		
10	Provide & casting reinforced concrete slab thick 12 cm mix 1:2:4 use rebar 4 lina in space 15cm c/c in both side , 4times/day/4days watering will be	Sqm	1.08		
11	Provide & build wall using, bricks high quality, strong, construction of wall will be in mix 1:8 cement & sand mortar ,3times/day/4days watering will be used	Sqm	25		
12	Provide & casting reinforced concrete slab thick 10 cm mix 1:2:4 use rebar 4 lina in space 15cm c/c in both side as latrines roof,4times/day/4days watering will be used.	Sqm	1.4		
13	Provide & fix plastic pipe for ventilation 12 bars capacity, to 75cm above the parapet as showing on the drawing.	PCs	1		
14	Provide & fix metallic exported manhole cover 50X50cm,	PCs	1		
15	Provide & install arabic toilet seat as best quality of materials.	PCs	2		
16	Provide & fix steel door size 70 * 180cm using steel hollow metal pipe 3*6cm heavy type 1mm thick, as well as metallic sheet 1mm include painting will be used.	PCs	2		
17	Provide & fix steel window size 40 * 40cm using steel hollow metal pipe 3*6cm heavy type 1mm thick, as well as 1mm thick wire mesh( rough) and fine one include painting .	PCs	2		
17	Provide & make plastering for internal & external wall by rate mix c/s 1:6 3times/day/3days watering will be used.	Sqm	50		
18	Provide & painting lime with emulsion paint for internal wall	Sqm	50		

19	Provide & construct latrines steps (2steps) 25cm height with 6.25m long & 30cm width using cement mortar in 1:8 rate 3times/day/3days watering will be used.	Job	1		
20	Cleaning of site and make good backfilling	Job	1		
	<b>Total COST for one school latrine with two drop holes</b>				
	<b>VAT17%</b>				
	<b>Total Cost including</b>				
	<b>TOTAL COST for three VIP latrines with two drop holes</b>				

Total Cost in USD(1USD= 565SDG)

Contractor Name: \_\_\_\_\_

Contractor Address: \_\_\_\_\_

Contractor Signature: \_\_\_\_\_