

**Name of the Work:****UNHCR Girba Office. First Floor Works.**

The specified job are all provisional, including provision of materials and workmanship, providing water and electricity for the implementation and all other requirements to implement the job perfectly. The bidder must visit the site prior to submission of bid documents. The cost of this item should be included /imbedded in the other items. All material should approve from engineer before supplying.

No.	Description	Unit	Qty	Unit price	Total Amount
<b>1</b>	<b>MOBILIZATION</b>				
1.1	Mobilization of labor, mobile workshop to be used for fixing maintaining and repairing of any kind of work such as steel, carpentry ...etc.	<b>Job</b>	<b>1</b>		
<b>2</b>	<b>SITE CLEARANCE</b>				
2.1	Clearing the site after completing the whole Job and before handover.	<b>Job</b>	<b>1</b>		
2.2	remove stair room from the red brick with zink roof and transfer of rubble off-site	<b>Job</b>	<b>1</b>		
2.3	remove the old layer (khafga) from the ground and cleaning the ground very well and the Transfer of rubble off-site	<b>Job</b>	<b>1</b>		
<b>3</b>	<b>Concrete Works:</b>				
3.1	supply material to iron implant with the old iron (like grout material) because we don't have a good overlap for a new bars, column include 6 bars	<b>Number</b>	<b>16</b>		
3.2	Supplying and casting a reinforced concrete column 50*25 cm as mixer (1:2:4) with heigh 3 m with the necessary reinforcement according to the engineer's directions	<b>Number</b>	<b>16</b>		
3.3	supply material and cast reinforced concrete (1:2:4) with steel bars for roof slab 20 cm rate include form works, steel works,elec work and all related works.	<b>M<sup>2</sup></b>	<b>230</b>		
	<b>Finishing Works:</b>				
<b>4</b>	<b>Masonry Works:</b>				
4.1	supply materials and build one brick for (parapet) walls with c/s mortar (1:6). Price including installation pipe for draining rain water from the roof.	<b>ML</b>	<b>52</b>		
4.2	supply materials and build one brick walls with c/s mortar (1:6) , including parapet when required, rate to include all related works like sills for door and window.	<b>M<sup>2</sup></b>	<b>430</b>		
<b>5</b>	<b>Plastering Works:</b>				
5.1	Supply materials and doing plaster walls C/S mortar (1:6) for external walls.reate include walls/corners plaster, windows and doors sills and all related works	<b>M<sup>2</sup></b>	<b>152</b>		
5.2	Supply materials and doing plaster walls C/S mortar (1:6) for enternal walls.reate include walls/corners plaster, windows and doors sills and all related works	<b>M<sup>2</sup></b>	<b>587</b>		
5.3	Supply materials and doing plaster walls C/S mortar (1:6) for roof .reate price include all related works	<b>M<sup>2</sup></b>	<b>230</b>		
<b>6</b>	<b>Plumbing Works:</b>				
6.1	Supply and installment pour flush seat high quality with all connection it need and accessories	Number	<b>4</b>		
6.2	Supply and installment hand wash high quality with water mixer and all connection it need and accessories	Number	<b>5</b>		

6.3	Supply and installment shower 80*80 cm with protection wall from fiberglass all accessories and connection	Number	1		
6.4	Supply and installment accessories for bath like mirror, soapseat ,bath towel seat	Number	4		
6.5	Supply and installment collection point (pepa) with all connection	Number	3		
6.6	Supply and installment Water mixer, and shower head from high quality with all connection	Number	1		
6.7	Supply and installment water pipeline network 3/4 with all fitting and connection	ML	40		
6.8	Supply and installment pipeline network 4 inch with all fitting and connection	ML	15		
6.9	Supply and installment pipeline network 2 inch with all fitting and connection	MI	12		
6.10	Supply and building manahole 60*60 cm with all connection	Number	2		
6.11	Supply and building manahole (gletrab) 30*30 with all connection	Number	2		
6.12	supply and install new water as 1000 Liter vertical withh all connections, Supply any materails its needed	Number	1		
6.13	shifting two water tank from the first floor to the second floor with all connections it needed. Supply any materails its needed	Number	2		
6.14	Supply and installment one suction fan in the kitchen (0.5*0.6) from Aluminium and all accessories.	Number	1		
6.15	supply and installation halazoni circlery stairs for up on last roof, (raising to up) as height 3 meter With all necessary installation	job	1		
7	<b>Tiles Works:</b>				
7.1	Provide and install floor tiles 40*40 cm spanish tiels or equivalent in the quality . With C/S mortar 1:8, for floors, baths & Kitchen floor rate include all related works	M <sup>2</sup>	214		
7.2	Provide and install walls tiles spanish tiels or equivalent in the quality . With C/S mortar 1:8, for walls rate include all related works	M <sup>2</sup>	138		
8	<b>Painting Works:</b>				
8.1	Supply materials and apply emulsion paint (suitable for interior and exterior walls) 3 layers of paint (selected colors) (all blocks), rate includes all related works	M <sup>2</sup>	1139		
9.1	<b>Electricity Works:</b>				
9.1	supply and fixing of Orient ceiling fan. with all necessary connections	Number	7		
9.2	supply and fixing of Socket 13 A. with all necessary connections	Number	18		
9.3	supply and fixing of Socket 16 A. with all necessary connections	Number	10		
9.4	supply and fixing of switch 45 A. with all necessary connections	Number	3		
9.5	supply and fixing of Lamps down light circular with chain for ceiling (high quality). With switch and all necessary connections	Number	8		
9.6	supply and fixing of Lamp 4 feet as good quality like philips. with all necessary connections	Number	10		
9.7	supply and fixing of ceiling lamp circular. with all necessary connections	Number	16		
9.8	Provide, fix and installation of new Main distribution board, main switch, 12 phase, with provide cable 16mm, all connected to main power lines. And all related electrical work.	Number	1		
9.9	checking and fixing external electrical like lamps and connection defects if any.include supply of some electrical items.	Job	1		
<b>Total amount</b>					