

Bill Of Quantities for construction School latrines(with two drops hall) in Keiba School

SN	Item Description	unit	Quantity	Unit Price	Total Price
	<u>Foundations</u>				
	Excavations should be as per standard technical specifications. Price is inclusive of planning, Excavations and filling of sides if necessary, removal of earth and disposal out of the site and clearance of beds to the required depth as per technical drawings.				
	Drilling in well at a dimension of 3.2*3m and a depth not exceeding 4m and located the excavated soil to selected location	Cum	22.4		
9	Provide & casting reinforce concrete beam section 20*20 cm mix 1:2:4, concrete beam will be Joining with external wall 6m*2.4m,4T12mm,c/c steel bars will be used as well, 4times/day/4days watering will be used.	M.L	33.5		
10	Provide & casting reinforced concrete slab thick 12 cm mix 1:2:4 use rebar 4 lina in space 15cm c/c in both side , 4times/day/4days watering will be	Sqm	1.08		
11	Provide & build wall using, bricks high quality, strong, construction of wall will be in mix 1:8 cement & sand mortar ,3times/day/4days watering will be used	Sqm	25		
12	Provide & casting reinforced concrete slab thick 10 cm mix 1:2:4 use rebar 4 lina in space 15cm c/c in both side as latrines roof,4times/day/4days watering will be used.	Sqm	1.4		
13	Provide & fix plastic pipe for ventilation 12 bars capacity, to 75cm above the parapet as showing on the drawing.	PCs	1		
14	Provide & fix metallic exported manhole cover 50X50cm,	PCs	1		
15	Provide & install arabic toilet seat as best quality of materials.	PCs	2		
16	Provide & fix steel door size 70 * 180cm using steel hollow metal pipe 3*6cm heavy type 1mm thick, as well as metallic sheet 1mm include painting will be used.	PCs	2		

17	Provide & fix steel window size 40 * 40cm using steel hollow metal pipe 3*6cm heavy type 1mm thick, as well as 1mm thick wire mesh(rough) and fine one include painting .	PCs	2		
17	Provide & make plastering for internal & external wall by rate mix c/s 1:6 3times/day/3days watering will be used.	Sqm	50		
18	Provide & painting lime with emulsion paint for internal wall	Sqm	50		
19	Provide & construct latrines steps (2steps) 25cm height with 6.25m long & 30cm width using cement mortar in 1:8 rate 3times/day/3days watering will be used, the steps should be fit for the people with disability.	Job	1		
20	Cleaning of site and make good backfilling	Job	1		
Total COST for one school latrine with two drop holes					
VAT17%					
Total including VAT17%					
TOTAL COST for two school latrines with two drop holes					

Total cost in USD(1USD= 565SDG)

Contractor Name: _____

Contractor Address: _____

Contractor Signature: _____