

Bill Of Quantities for construction VIP latrines(with two drops hall) in Jawa School

| SN | Item Description | unit | Quantity | Unit Price (SDG) | Total Price (SDG) |
|----|--|------|----------|------------------|-------------------|
| 1 | Provide & casting reinforce concrete beam section 20*20 cm mix 1:2:4, concrete beam will be Joining with external wall 6m*2.4m,4T12mm,c/c steel bars will be used as well, 4times/day/4days watering will be used. | M.L | 33.5 | | |
| 2 | Provide & casting reinforced concrete slab thick 12 cm mix 1:2:4 use rebar 4 lina in space 15cm c/c in both side , 4times/day/4days watering will be | Sqm | 1.08 | | |
| 3 | Provide & build wall using, bricks high quality, strong, construction of wall will be in mix 1:8 cement & sand mortar ,3times/day/4days watering will be used | Sqm | 25 | | |
| 4 | Provide & casting reinforced concrete slab thick 10 cm mix 1:2:4 use rebar 4 lina in space 15cm c/c in both side as latrines roof,4times/day/4days watering will be used. | Sqm | 1.4 | | |
| 5 | Provide & fix plastic pipe for ventilation 12 bars capacity, to 75cm above the parapet as showing on the drawing. | PCs | 1 | | |
| 6 | Provide & fix metallic exported manhole cover 50X50cm, | PCs | 1 | | |
| 7 | Provide & install arabic toilet seat as best quality of materials. | PCs | 2 | | |
| 8 | Provide & fix steel door size 70 * 180cm using steel hollow metal pipe 3*6cm heavy type 1mm thick, as well as metallic sheet 1mm include painting will be used. | PCs | 2 | | |
| 9 | Provide & fix steel window size 40 * 40cm using steel hollow metal pipe 3*6cm heavy type 1mm thick, as well as 1mm thick wire mesh(rough) and fine one include painting . | PCs | 2 | | |
| 10 | Provide & make plastering for internal & external wall by rate mix c/s 1:6 3times/day/3days watering will be used. | Sqm | 50 | | |
| 11 | Provide & painting lime with emulsion paint for internal wall | Sqm | 50 | | |

| | | | | | |
|----|---|-----|---|--|--|
| 12 | Provide & construct latrines steps (2steps) 25cm height with 6.25m long & 30cm width using cement mortar in 1:8 rate 3times/day/3days watering will be used. | Job | 1 | | |
| 13 | Cleaning of site and make good backfilling | Job | 1 | | |
| | Total COST for one school latrine with two drop holes | | | | |
| | VAT17% | | | | |
| | Total Cost including VAT17% | | | | |
| | TOTAL COST for three VIP latrines with two drop holes | | | | |

Total Cost in USD(1USD= 565SDG)

Contractor Name: _____

Contractor Address: _____

Contractor Signature: _____