

**UNHCR**United Nations High Commissioner for Refugees
Haut Commissariat des Nations Unies pour les réfugiés**ANNEX C – FINANCIAL OFFER FORM: RFP/HCR/KAD/SUP/2022/09**

The bidders are requested to fill in the price information in the below table. Bidders also are requested to fill in legislative information below the table:

No.	DESCRIPTION	UNIT	QTY	Unit Price (USD)	Total Price (USD)
1.0	MOBILIZATION				
1.1	Mobilization and Demobilization of labor/machinery workshop for fixing, fabrication, and maintaining of any kind of work such as formwork concrete, steel, carpentry ...etc.	JOB	1		
2.0	SITE CLEARANCE				
2.1	Cleaning the site after completing the whole job and before handover.	JOB	1		
3.0	BUILDINGS WORKS				
3.1	Excavation required depth for foundation 50(width)*70(depth)cm rate includes disposal of away or selected approved area, as per normal standard and UNHCR engineer instruction.	ML	114		
3.2	Supply material and lay stone foundation with c/s mortar (1:8) 50 cm depth, 50 cm width, by 2 stages 25 cm each, as per normal standard and UNHCR engineer instruction.	ML	114		
3.3	Supply materials and building red brick continue foundation (two bricks system) with c/s mortar (1:6) width of wall 40cm, hheight40 cm, as per normal standard and UNHCR engineer instruction.	ML	114		
3.4	Supply materials and cast reinforced concrete Grade beam (1:2:4) with 6 steel 12mm bar for continues foundation 30*40cm and use 8mm steel bar for Stirrup, rate to include conc. steel, formation work, steel work and related works, as per normal standard and UNHCR engineer instruction.	M3	13.68		
3.5	Supply materials and build bricks wall of red brick with c/c mortar (1:8) width of 30cm (one and a half brick system) including parapet, work to include all related works, as per normal standard and UNHCR engineer instruction	M2	324		
3.6	Supply materials and cast reinforced concrete (1:2:4) with 4ø12mm steel bars for tie beams 30*20cm and use 8mm steel bar for Stirrup @ 200 mm, rate to include concrete \, steel, formwork, steel work, and all related works, as per normal standard and UNHCR engineer instruction.	M3	6.84		
3.7	Supply materials and cast reinforced concrete (1:2:4) with 4ø12mm steel bars for ring beam 30*20cm and use 8mm steel bar for Stirrup @ 200 mm, rate to include concrete, steel, formwork, steel work, and all related works, as per normal standard and UNHCR engineer instruction.	M3	6.84		
3.8	Supply materials and fill sub-base layer of selected material underground slab of 40cm, rate includes leveling, watering, and compaction by 2 layers 20cm each, as per normal standard and UNHCR engineer instruction.	M3	75.2		
3.9	Supply materials and cast 10 cm thick concrete (1:3:6) for the ground slab, including a steel grid with 8 mm steel bars at 20 cm in both direction, (including the waiting area)work include all related works, as per normal standard and UNHCR engineer instruction.	M2	188		

3.10	Supply materials and plaster walls c/s mortar (1:6) for internal and external walls, rate include walls edge /corners plaster windows and doorsills and all related works, complete job, as per normal standard and UNHCR engineer instruction.	M2	200		
3.11	Supply materials and fabricate steel grid from rectangular steel pipes 4*8 cm and 6*3 cm 1mm, for roof support grids, the work includes fixing, anti-rust paint, paint, fixing on the tie beams using bolts and all necessary accessories the work includes supply materials and fix a pre-painted corrugated sheets steel sheets .35mm the blue color, as shown in the design, fixing on the purlins, trusses drilled nails with washer and all necessary accessories, as per normal standard and UNHCR engineer instruction.	M2	188		
3.12	Supply and fix suspended ceiling from gypsum board square tiles 60x 60 cm, and Aluminium frames T profile, and the suspended hanging system, including aluminum L profile. The sample is to be presented prior to installation, as per normal standard and UNHCR engineer instruction.	M2	188		
4.0	DOORS AND WINDOWS				
4.1	Supply and fix (100*220) size new solid steel door, locally made, using heavy steel for door and frames as in attached design, covered with heavy steel sheet, price to include, fixing with hinges, locking system, paint,...etc, as per normal standard and UNHCR engineer instruction.	NO.	2		
4.2	Supply and fix (120*220) size new solid steel door, locally made, using heavy steel for rectangular pipes for doors and frames as in attached design covered with heavy steel sheet, price to include, fixing with hinges, locking system, paint,...etc, as per normal standard and UNHCR engineer instruction.	NO.	6		
4.3	Supply material and fabricate (120*120) size new steel new windows, locally made, using heavy steel for frames, covered with a ribbed steel plate with horizontal grills made of 4*8 cm pipes, price to include, fixing with hinges, locking system, paint grills ...etc, as per normal standard and UNHCR engineer instruction.	NO.	23		
5.0	FINISHING WORKS				
5.1	Supply materials and apply quick drying prime (internal walls only) two coats to make the surface of walls adhesive to receive new paint, as per normal standard and UNHCR engineer instruction.	M2	200		
5.2	Supply materials and apply paint (suitable for interior and exterior walls) 2 layers of paint (selected color) (main blocks), rate includes all related works, as per normal standard and UNHCR engineer instruction.	M2	400		
6.0	ELECTRICAL WORKS & EXTRA FINISHING WORKS				
6.1	Provide for supply, installation and all cables and sockets (as sown in drawings) required for a complete electrical work including PVC conduits provide for armored connection cable from the building to the nearest power source. The rate should include excavation, laying, and connection with cable cleats, as per normal standard and UNHCR engineer instruction.	LS	1		
6.2	Supply and install Ceiling mounted sweep fan with all Accessories like wall-mounted Speed Control, non-corrosive type blades, regulator, fan hook, extension rod, and all other accessories required. The minimum fan-to-floor distance shall be 230cm. The rice shall include PVC insulated conductors of 3x2.5mm ² inside PVC conduit of 16mm diameter including junction boxes with covers and insulating screw cap connectors The rate should include excavation, laying, and connection with cable cleats, as per normal standard and UNHCR engineer instruction.	LS	9		
6.3	Light Fittings and Lamps: lamps Supply, install and connect wall lights of LED Wall lamps 15 w in buildings as shown in the drawings with the wiring of 2x2.5mm ² cable inside PVC conduit of 16mm diameter, the work includes digging installing (installation before finishing works), lamps key for opening and closing, and all needed finishing works, as per normal standard and UNHCR engineer instruction.	LS	22		

6.4	Supply and install an approved type of LED roof light lamps Lighting,15W. The rate should include fixing on the roof, installing keys for opening and closing, wiring, laying, and connection with cable cleats, as per normal standard and UNHCR engineer instruction.	LS	6		
6.5	Supply material and fill sub-base layer of selected materials for the corridor, 50 m2, 40 cm height, rate includes leveling, watering and compaction by 2 layers 20 each, as per normal standard and UNHCR engineer instruction.	M3	20		
6.6	Supply and install concrete block (interlock) at the corridor, the total area is 50 m2, the rate includes all needed works, as per normal standard and UNHCR engineer instruction.	M2	50		
6.7	Supply materials and cast conc.3 Steps 150cm wide and 15 cm height @ (entrance), with length 1m, rate includes all related works, as per normal standard and UNHCR engineer instruction.	LS	1		
6.8	Supply materials and cast Construct 1 ramp for disabled people as shown in the drawing, with a slope of 1:08 with a maximum length of 3.5-4 meters and width not less than 90 cm, using 8mm steel bars, 15 cm mesh in both directions as fine reinforcement, handrails should also be installed to protect and facilitate the use of ramps, the work includes site cleaning before and after construction and all necessary finishing works, as per normal standard and UNHCR engineer instruction.	LS	1		
7.0	FENCE WORKS				
7.1	Supply material and fabricate chain link fence as shown in the drawing, 1.8-meter height. 3" steel pipes supporter @ 2 meters, fixed by 40x40x50 cm concrete base rate attached to wire mesh 25cm and linked to steel pipes using Knot every 1m to ensure good fixing as shown in drawings, as per normal standard and UNHCR engineer instruction.	ML	41		
7.2	Supply material and fabricate the main gate with a locking system linked to the fence as shown in the drawing,3m width (2 doors with support and lock in the middle), 1.8-meter height. 3" steel pipes for both frame and stands, fixed by 60x60x60 cm concrete base, rate including all needed works, as per normal standard and UNHCR engineer instruction.	LS	1		
7.3	Supply material and fabricate pedestrian gate with locking system linked to the fence as shown in drawing,1.2m width, 1.8-meter height. 3" steel pipes for both frame and stands, fixed by 60x60x60 cm concrete base rate including all needed works as per normal standard and UNHCR engineer instruction.	LS	1		
8.0	LATRINE (5 STANCE)				
8.1	Excavation of pit with dimensions (3*3*6) m, the work includes disposal of excavated materials to an approved area away from site location, as per normal standard and UNHCR engineer instruction.	M3	54		
8.2	Supply and construction of a pit lining with (1.5) bricks with cement mortar (1:8) including dividing walls, as per normal standard and UNHCR engineer instruction.	M2	63		
8.3	Supplying and casting concrete (1:3:6) for the pit and floors (10cm) and making Cement coating, as per normal standard and UNHCR engineer instruction.	M2	26		
8.4	Supplying and placing Reinforcement concrete (1:2:4) for the latrine slab using 12mm bars 12cm grid c/c for reinforcement, as per normal standard and UNHCR engineer instruction.	M2	18		
8.5	supplying and making a plaster with cement mortar (1:6) for the inside the pit, as per normal standard and UNHCR engineer instruction.	M2	90		
8.6	Excavation of foundation trench (0.5*0.5), the work includes the disposal of excavated materials to an approved area away from the site location, as per normal standard and UNHCR engineer instruction.	ML	40		
8.7	Supply and construction of a single-brick wall with cement mortar (1:8) for rooms (including divides walls), as per normal standard and UNHCR engineer	M2	67.5		

	instruction.				
8.8	Supply and casting of concrete (1:2:4) for the door beam reinforced with steel bars 12mm (4 bars), as per normal standard and UNHCR engineer instruction.	ML	24		
8.9	Supply, manufacture, and installation of zinc roofing corrugated steel sheet with 0.35 mm thick fixed by square pipes (4*8) including fixing bolts (4*8), the work includes pre-painting, fixing on the rafters using all necessary plates, bolts, welding, and accessories, as per normal standard and UNHCR engineer instruction.	M2	15		
8.10	Supplying and making plaster with cement mortar (1:8) for the walls inside and outside the rooms, isolation walls, and all parapets, as per normal standard and UNHCR engineer instruction.	M2	126		
8.11	Supplying and installing steel doors with a skylight size (0.7 * 2.2) meters for the doors of normal rooms, as per normal standard and UNHCR engineer instruction.	No	4		
8.12	Supply and installation of a steel door with a skylight size (1*2.2) meters for people with special needs room, as per normal standard and UNHCR engineer instruction.	No	1		
8.13	Supplying and painting the wall inside and out (the color is white with a blue stripe on the top line, as per normal standard and UNHCR engineer instruction.	M2	126		
8.14	Supply and installation of ventilation pipes with meshed cover.	No	5.0		
8.15	Supplying and installing facilities for people with disabilities, -iron seat, -handrail along the room. as per normal standards and UNHCR engineer instruction.	LS	1.0		
8.16	Supplying and installing toilet ceramic seats of an approved type, as per normal standard and UNHCR engineer instruction.	No	5.0		
8.17	Supply material and construct a sub-base layer of selected material under the corridor ground slab of 35 cm, work includes leveling and compaction, as per normal standard and UNHCR engineer instruction.	M3	4.0		
8.18	Supply materials and cast 10 cm thick plain concrete (1:3:6) for corridor slab, as per normal standard and UNHCR engineer instruction.	M3	1.5		
8.19	Supply and construction of ramp to special need people room with handrail, as per normal standard and UNHCR engineer instruction.	No	1.0		
9.0	EXTERNAL FLOOR				
9.1	Supply materials and backfill of the compound to ensure floor protection with the selected material height of 30cm, rate including leveling and compaction, as per normal standard and UNHCR engineer instruction.	M2	204		
10.0	HANDWASHING BASIN				
10.1	Supply materials and build 2 basins for hand washing attached to latrines, with 2 water taps, the height should be suitable to disabled people, the work includes piping from the elevated water tank located in the women's center with all needed fittings, as per normal standard and UNHCR engineer instruction.	LS	1.0		
11.0	FESIBILITY WORKS				
11.1	Supplying and installing a signboard (1 * 1) meters of iron sheet, indicating the name of the project, the donor, and the implementer, as per normal standard and UNHCR engineer instruction.	No	1.0		
Total Amount					



I hereby accept UNHCR payment terms, offer validity, and contractual provisions that are stipulated in this RRP document:

YES NO

Total amount: _____

Total amount in words: _____

Date: _____

Supplier/company name: _____

Contact name & tittle: _____

Contact phone number: _____

Contact email address: _____

Signature: _____

Duly authorized to
Sign bid for and on behalf of: _____

Official stamp: _____