

# Request for Quotation

عرض الاسعار

FROM من	NORWEGIAN REFUGEE COUNCIL
Address العنوان	Sudan – Gadarif – East Aljbarab
City المدينة	Gadarif
Country الدولة	Sudan
Phone # الهاتف	0912975110
Email بريد الكتروني	<a href="mailto:sd.procurement.gadarif@nrc.no">sd.procurement.gadarif@nrc.no</a>

TO الى العمل \ الشركة	
Address العنوان	
City المدينة	
Country الدولة	
Phone # الهاتف	
Email بريد الكتروني	

The office of the Norwegian Refugee Council invites your company to submit a price quotation for the following items in accordance with the requirements detailed below. You may use your company format, or fill up the table below. Please read carefully the instructions on page 20

Request for Quotation Requirements (To be filled by NRC Procurement staff)			
Rehabilitation of latrine in different sites in Gadarif as BOQ			
RFQ # : عرض الاسعار	PF - GAD-682- 034 - PR 8501487	Currency العملة	
RFQ Issuing Date: تاريخ الاصدار	15/06/2025	Bid Validity Period (days): (Preferably 30 days) صلاحية السعر المنظمة تفضل 30 يوم	
RFQ Closing Date: تاريخ الاغلاق	17 /06/2025	Required Delivery Date: (التنفيذ) زمن التوصيل	
RFQ Closing Time: زمن الاغلاق	14:00 PM	Required Delivery Destination: جهة التسليم	NRC office – Gadarif – East Jubarab
Questions to the RFQ للاستفسار	<a href="mailto:sd.procurement.gadarif@nrc.no">sd.procurement.gadarif@nrc.no</a>	Required Delivery Terms: شروط التسليم المطلوبة	

**BOQ for Latrine Rehabilitation**

1\Name of the gathering site: Salamat Albeh school for Boys

Number of latrine pits:6

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					
1	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks for 6 doors .	Job	6		
2	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	155		
3	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	20		
4	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	1		
5	Supply materials , replace damaged wall and construct a two-brick sand cement mortar wall with a mix ratio of 1:6( wall dimensions: 2 x 4.33)m2.	m2	8.66		
6	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	Job	1		
Total					

**BOQ for Latrine Rehabilitation**

2\Name of the gathering site: Salamat Albeh school for girls

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications					
1	Supply and install metal doors size (0.74*1.80)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	4		
2	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	2		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	76		
5	Plumbing maintenance( provide and install ventilation pipes.).	No	1		
6	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

3\Name of the gathering site: Almotamr school for girls

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications					
2	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	2		
3	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external lock.	No	4		

4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	82		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	82		
7	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

#### BOQ for Latrine Rehabilitation

4\Name of the gathering site:Abakr jebril for boys

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					
1	Supply and install metal doors size (0.75*1.70)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	1		
2	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks	No	4		
3	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	100		
4	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	100		

5	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

**BOQ for Latrine Rehabilitation**

5\Name of the gathering site:Abakr jebri for girls

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications					
1	Supply and install metal doors size (0.75*1.70)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	4		
2	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	82		
3	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	82		
4	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

**BOQ for Latrine Rehabilitation**

6\Name of the gathering site: Al Abasiaa almtwsta school for girls

Number of latrines pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					
1	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	4		
2	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks for 6 doors .	No	4		
3	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	63		
4	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	63		
5	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

7\Name of the gathering site: Al Abasiaa School For Boys

Number of latrines pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					
1	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	1		

2	Doors maintenance ( Provide Lock for Doors & install them)	No	1		
3	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks	No	4		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	73		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	73		
6	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

8\Name of the gathering site:Altdamon almzdwaja Elementary School for Girls

Number of latrines pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					
1	Supply and install metal doors size (0.75*1.70)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	4		
2	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	3		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	51		

5	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

**BOQ for Latrine Rehabilitation**

9\Name of the gathering site:Altdamon secondary school for girls

Number of latrine pits:6

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications					
1	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks	No	6		
3	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	217		
4	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

**BOQ for Latrine Rehabilitation**

10\Name of the gathering site: Albaan jaded scool

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price(	Total Price(
Work should be done as per standard technical specifications.					
1	Supply and install metal doors size (1.80*0.65)cm with frame size 60x30x1mm and leaf of metal plate 8 mm	No	4		



	thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality				
2	Plumbing maintenance( provide and install ventilation pipes.).	No	2		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	74		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	74		
6	Supply and erect steel window with mesh sheet for latrine mesh, properly to ensure eliminating any flies as per engineer instruction and satisfaction	NO	2		
7	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

11\Name of the gathering site: Altdamon aljadedda

Number of latrine pits:15

#NO	Description	Unit	Quantity	Unit Price(	Total Price(
Work should be done as per standard technical specifications					
1	Supply and install metal doors size (2*0.80)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	1		
2	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	9		

3	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks	No	15		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	273		
6	Supply and erect steel window with mesh sheet for latrine mesh, properly to ensure eliminating any flies as per engineer instruction and satisfaction	NO	2		
7	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

12\Name of the gathering site: Aljenena school for girls

Number of latrine pits:8

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					
1	Supply and install metal doors size (1.73*0.78)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	1		
2	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	1		
3	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks	No	8		

4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	135		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	135		
7	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

13\Name of the gathering site: Aljamark school

Number of latrine pits:6

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					
1	Supply and install metal doors size (1.80*0.75)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	6		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	97		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	97		
7	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		

Total	
-------	--

**BOQ for Latrine Rehabilitation**

14\Name of the gathering site: Al tadamoon school for boys

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					
1	Supply and install metal doors size (1.76*0.64)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	4		
2	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	4		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	78		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	78		
7	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

**BOQ for Latrine Rehabilitation**

15\Name of the gathering site: Aljamhoria School For Boys

Number of latrines pits:7

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications.					

1	Supply and install metal doors size (1.80*0.87)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	7		
2	Supply (0.50x0.50) cm manhole covers.	No	1		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	217		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	134		
6	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

16\Name of the gathering site: Gharikana School For Boys

Number of latrines pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications					
3	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks	No	4		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	90		
5	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light	job	1		

	bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction				
Total					

**BOQ for Latrine Rehabilitation**

17\Name of the gathering site: Yathrib school

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications					
1	Supply and install metal doors size (1.80*0.74)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	1		
2	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	4		
3	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks	No	4		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	70		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	70		
6	Supply and erect steel window with mesh sheet for latrine mesh, properly to ensure eliminating any flies as per engineer instruction and satisfaction	NO	4		

7	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

**BOQ for Latrine Rehabilitation**

18\Name of the gathering site: 6 April school

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications					
1	Doors maintenance ( Provide Lock for Doors & install them)	No	1		
2	Supply materials, weld, repair and coat exist steel doors 200 x 80 cm, painting in two layers paints internal and external sides, cost shall include all necessary welding extra reinforcement and repair of internal and external locks	No	4		
3	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	60		
4	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	1		
5	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

**BOQ for Latrine Rehabilitation**

19\Name of the gathering site: Alboqa school

Number of latrine pits:4

#NO	Description	Unit	Quantity	Unit Price)	Total Price(
Work should be done as per standard technical specifications					
1	Supply and install metal doors size (1.80*0.75)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	4		
2	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	4		
4	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	76		
5	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	76		
6	Plumbing maintenance( provide and install ventilation pipes.).	No	2		
7	Supply and erect steel window with mesh sheet for latrine mesh, properly to ensure eliminating any flies as per engineer instruction and satisfaction	NO	4		
8	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

20\Name of the gathering site: Alsdaga2

Number of latrines pits:4

#NO	Description	Unit	Quantity	Unit Price	Total Price(
Work should be done as per standard technical specifications					



1	Supply and install metal doors size (1.80*0.60)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	4		
3	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	4		
4	Supply and erect steel window with mesh sheet for latrine mesh, properly to ensure eliminating any flies as per engineer instruction and satisfaction	NO	4		
5	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	67		
6	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	67		
7	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

### BOQ for Latrine Rehabilitation

21\Name of the gathering site: Almotamr school for boys

Number of latrine pits:8

#NO	Description	Unit	Quantity	Unit Price	Total Price(U
Work should be done as per standard technical specifications					
1	Supply and install metal doors size (1.80*0.75)cm with frame size 60x30x1mm and leaf of metal plate 8 mm thick with frame,with hinges, internal and external locks of good including 2 coats of metal paint. quality	No	3		
2	doors maintenance ( including 2 coats of metal paint, internal & external& doors instaltion)	No	5		

3	Supply and erect steel window with mesh sheet for latrine mesh, properly to ensure eliminating any flies as per engineer instruction and satisfaction	NO	4		
4	Provide doors mesh, measuring (0.50*0.15)	NO	1		
5	Supply materials, fix in position and test Arabic water closet (stance), according to specifications and engineer instructions.	No	4		
6	Provide materials and apply 3 coats(primary, undercoat and finishing) emulsion paint to walls internally and externally	M2	168		
7	Supply materials, cast and apply cement / sand plaster layer; 20 mm thickness in two layers, 1:6 cement : sand mix finished smooth for supporting the doors frame and repairing exist plaster, as per the Technical Specifications .	M2	75		
8	Supply and repair exist electrical wiring including replacing damaged or installation of new 10W LED light bulbs inside/outside latrine with boards as per engineer instruction and to NRC satisfaction	job	1		
Total					

**TOTAL COST for 112 pit : .....**

Delivery Lead Time (in days, from receipt of NRC Purchase Order) فترة التوصيل أو التنفيذ بالايام	
Bid Validity Period (in days from receipt of NRC Purchase Order): صلاحية السعر بالايام بعد التوقيع على امر الشراء	
Defects liability and guarantee period: فترة الضمان ملحوظة ( للاجهزة والمعدات والانشاءات )	
Country of origin of the goods بلد المنشأ او الانتاج ان وجد	
Name الاسم	
Position الوظيفة	
Date Signature Stamp التاريخ - التوقيع - الختم	

### RFQ Terms & Conditions

#### Manner of Submission:

By email to the dedicated and secured email address

[sd.procurement.gadarif@nrc.no](mailto:sd.procurement.gadarif@nrc.no)

- (offers received on other email addresses will not be considered)
- Before the Closing date & Time mentioned above. Companies who do not submit their quotation by this deadline will not be considered

التقديم عبر الايميل اعلاه فقط ولايعتبر التقديم عبر الايميلات الشخصية وبعد انتهاء فترة التقديم

#### Requirements:

- All Bids must include all customs and taxes payable in the country of delivery unless the RFQ specifically requests differently
- Bids must be submitted in the currency indicated in the RFQ. Bids in other currency might not be accepted
- Bids must be valid for the validity period indicated in the RFQ. Bids not meeting this validity period might be disqualified
- All enquires and questions should be addressed to the email given in the RFQ details section. All questions and answers will be shared with all invited suppliers.
- NRC reserves the right to accept or reject the whole or part of your quotation based on the information provided. Incomplete quotations which do not comply with our conditions will not be considered.

#### Mandatory documents:

Requested document	Check (Y/N)
Company registration Certificate شهادة تسجيل	
Vat Registration Certificate التسجيل في القيمة المضافة	
Tax registration certificate الرقم التعريفي الضريبي	
Passport Copy / ID of company director صورة من أثبات الشخصية \ جواز بطاقة قومية	
Copies of relevant Experience relevant Activates خبرة سابقة في المجال ان وجد	
NRC RFQ to be signed and stamped in each page التوقيع والختم في كل الصفحات	

Technical Specification photo attached صورة مرفقة من المواصفات الفنية	
Ethical Standards Signed and Stamped المعايير الأخلاقية توقع وتختتم لمن يرسو اليه المناقصة او العطاء	

**Assessment Criteria:**

- All bids received and accepted will be evaluated based on the following:
- **Step 1:** Administrative compliance check: Each bid will be checked to ensure compliance with all the RFQ requirements
- **Step 2:** Technical Evaluation: All bids will be technically evaluated based on “best value for money”
- **Step 3:** Financial Evaluation: Price in comparison to NRC established expectation and in comparison, to other bidders of comparable technical quality

**Payment terms:**

- Payment will be made within **30 days** of receipt of goods, by **bank transfer/cheque only**.  
سيتم الدفع خلال 30 يوم بعد استلام المواد أو انجاز الاعمال بواسطة التحويل البنكي أو الشيك

<p>NRC is obliged to ensure that its procurement decisions are clearly justified and documented and keeping within the Donors mandatory principles. In that regard, full and on-the-spot access must be granted to representatives of NRC, the Donor or any organisation or person mandated by it, to premises belonging to NRC or its contractors. The right to access shall include all documents and information necessary to assess, or audit the implementation of the contract.</p> <p>NRC also expects suppliers who process personal data to comply with the General Data Protection Regulation (EU GDPR) and any relevant national legislation. Suppliers processing personal data on an NRC contract will be required to sign a data processing / sharing agreement as part of the contract. Refusal to sign such an agreement constitutes refusal of the contract terms and forfeiture of the contract on the part of the supplier.</p> <p>If the activities of the contract take place in areas with Explosive Hazards, NRC accepts no liability for injury and/or death to contractor's staff or damage to contractor's property.</p>	<p>Anti-money laundering, anti-bribery, anti-corruption and anti-terrorism legislation and donor regulations require NRC to screen contractors against various international lists to ensure due diligence. Submission of the quotation constitutes acceptance of these screening practices.</p> <p>NRC aims to purchase products and services with minimum environmental impact. Environmental considerations form part of the NRC selection criteria, and NRC reserves the right to reject quotations provided by suppliers not meeting these standards.</p> <p>All suppliers doing business with NRC should maintain high standards on ethical and environmental issues, respect and apply basic human and social rights, ensure non-exploitation of child labour, and give fair working conditions to their staff. <b><u>Suppliers will be required to sign and submit an Ethical Standards Declaration, together with their bid.</u></b></p> <p>NRC reserves the right to reject quotations provided by suppliers not meeting these standards.</p>
--	---