

Request for Quotation

FROM	NORWEGIAN REFUGEE COUNCIL
Address	White Nile State, Kosti, Area Office
City	Kosti
Country	Sudan
Phone #	+249962593663
Email	sd.procurementskao@nrc.no

Kindly fill this information	
Supplier name	
Address	
City	
Country	
Phone #	
Email	

The office of the Norwegian Refugee Council invites your company to submit a price quotation for the following service in accordance with the requirements detailed below. You may use your company format or fill up the table below. Please carefully read the instructions on page **8**.

Request for Quotation Requirements			
RFQ #:	PF-KSI-A0-805	Currency	USD - SDG
RFQ Issuing Date:	November 4, 2025	Bid Validity Period (days):	Preferably 30 days
RFQ Closing Date:	November 9, 2025	Required Delivery Date:	30 days
RFQ Closing Time:	04:00 PM (GMT +2)	Required Delivery Destination:	Kosti Locality Goz Alsalm IDPs camps / Goli locality (WD SHMAM - Altbrat - Awd Allah)
Questions to the RFQ	sd.procurementskao@nrc.no	Required Delivery Terms:	Certificate of Completion

BoQ for Installation/ Rehabilitation 3 of Water Points & Donkey cart filling stand at Guli locality (WD SHMAM - Altbrat - Awd Allah)-BoQ for Installation/ Rehabilitation 7 of Water Points with Pipeline Extension in GOZ alsalam IDP's camp

	BoQ for Installation/ Rehabilitation 3 of Water Points & Donkey cart filling stand at Guli locality (WD SHMAM - Altbrat - Awd Allah)-BoQ for Installation
--	---

S.NO	DESCRIPTION	QUANTITY	UNIT	UNIT Rate	Total
------	-------------	----------	------	-----------	-------

The Contractor shall refer to all drawings and tender documents, including the specifications, and shall comply with all requirements contained therein. This includes, but is not limited to, the satisfactory completion of the Works in accordance with the approval of NRC Engineer and all relevant statutory authorities (SWC, WES), regardless of whether such requirements are explicitly stated in the Bill of Quantities.

Rehabilitation of (1) Donkey cart filling stand with connection to the elevated water tank at WD SHMAM Village

1	Area setting and backfilling				
1.1	Backfilling with selected material (hmari) in layers with compaction according to the design, technical specifications and engineer satisfaction	8.0	M3		
1.2	Backfilling with selected material (semsemia gravel) in layers according to the design, technical specifications and engineer satisfaction	3.2	M3		
2	Water Connections to the elevated water tank				
2.1	Supply material and connect 2 inch HDPE from the 4 existing pipe line with a reducer 3*3 and a union cluded all labor works	30.0	m		
2.2	Supply material and install 2 inch galvanized union and nable	4.0	No		
2.3	Supply material and install 2 inch galvanized elbows 45 & 90	2.0	No		

Installation of (1) Donkey cart filling stand at altbrat Village

	Donkey cart filling stand :				
1	Reinforced concrete footing				
1.1	Supply, cast and construct reinforced concrete footing 0.80 × 0.80 m, thickness 0.30m (Grade 35 N/mm²). Include T12 reinforcement @250 mm c/c both ways, formwork, curing, sampling & testing, mix design, labor, and all works per drawings and NRC specifications.	0.19	M3		
2	Plain concrete				
2.1	Supply, cast and construct plain concrete slab 0.60 × 0.60 m, thickness 0.15 m (Grade 20 N/mm²). Include formwork, curing, testing, ready-mix or in-situ concrete, labor, etc.	0.1	M3		
2.2	Supply, cast and construct plain concrete block/stand 0.30 × 0.30 × 0.60 m (Grade 20 N/mm²). Include formwork, curing, testing, ready-mix or in-situ concrete, labor, as drawings and NRC specifications.	0.1	M3		
3	Masonry works				
3.1	Supply materials and build 1½ -brick-thick wall made from red brick wall using cement: sand mortar 1:6 to height 0.60 m, length as per drawing. Provide workmanship, curing and to Engineer's satisfaction.	2.4	M2		
3.2	Supply materials and build 1½ - brick thick around the water point made from red brick wall using cement: sand mortar 1:6 to height 0.50 m, length as per drawing. Provider workmanship, curing and to Engineer's satisfaction.	4.0	M2		
4	Piping connections 2" HDPE (connection from existing)				
4.1	Supply lay and connect 2" HDPE pipe to the existing pipeline, including all one adapter from 3 -inch to 2-inch pipeline couplers and labour. as per specifications	30.0	ML		
4.2	Supply and install a cart filling stand – 2" GI vertical pipe 3.0 m high, , panting and accessories.	1.0	Jop		

4.3	Supply and install cart filling stand – 2" GI horizontal pipe, 5 m length, 3.0 m flexible hose, ball valve and union, mounting bracket, painting and accessories.	2.0	Jop		
6.3	Supply material and install 2-inch galvanized valve for the cart-filling stand	1.0	No		
6.4	Supply material and install 2 inch galvanized union and Naple	2.0	No		
6.5	Supply material and install 2 inch galvanized elbows 45 & 90	2.0	No		
6.5	Supply material and install 2 inch galvanized T	1.0	No		
5	Plastering Work: Supply materials and apply 2 cm (cement: sand) plaster in two coats (1:6) finished smooth on brick walls and exposed concrete surfaces as shown in drawings and as per technical specifications and to NRC Engineer's satisfaction.	1.4	m2		
6	Painting: Supply materials and apply primer coat + two coats of emulsion paint on prepared plaster/concrete surfaces as per spec; colours decided on-site. All works to be carried out as per technical specifications and to NRC Engineer satisfaction	1.4	m2		
Rehabilitation of (1) Water point rehabilitation at AWAD ALLAH					
1	Area setting and backfilling				
1.1	Backfilling with selected material (hmari) in layers with compaction according to the design, technical specifications and engineer satisfaction	4.5	M3		
1.2	Backfilling with selected material (semsemia gravel) in layers according to the design, technical specifications and engineer satisfaction	1.8	M3		
2	Masonry works				
2.1	dismantle and rebuild with the same break a foundation for tape stand (1*.6*1.5) wall with cement and sand mortar 1:6 according to , technical specifications and engineer satisfaction	4.5	ML		
3.2	Supply materials and build 1½ - brick thick around the water point made from red brick wall using cement: sand mortar 1:6 to height 0.50 m, length as per drawing. Provide workmanship, curing and to Engineer's satisfaction.	4.0	M2		
3.3	Supply materials and build 1½ - brick thick support stand on the water point sides to hold the pipe for .5 Hight to Engineer's satisfaction.	0.5	M2		
5	Drainage Pipe				
5.1	Supply material and construct a drainage PIPE 4 INCH PVC (6 m) to the nearest proper area or tree as per the community consultation	1.0	No		
6	Water Connections				
6.1	Supply material and make all connection works from Galvanized 2 inch pipes 6 meter length for the stand with a number of 6 water taps 1 inch from galvanized steel	1.0	No		
6.3	Supply material and connect 3 inch galvanized valve for tape stand	1.0	No		
8	Plastering Work: Supply materials, cast, and apply a 20 mm thick cement/sand plaster layer in two coats (1:6 cement-sand mix), finished smooth on the brick walls constructed and casted	4.8	m2		

	reinforced concrete , as per technical specifications and to NRC Engineer satisfaction				
9	Painting: Supply materials, mix, and apply two coats of emulsion paint on well-prepared plaster, with a primer lime coat and oil-based finish. Colors to be decided on-site. All works to be carried out as per technical specifications and to NRC Engineer satisfaction	9.6	m2		
BoQ for Installation/ Rehabilitation 7 of Water Points with pipeline extension					

S.NO	DESCRIPTION	QUANTITY	UNIT	UNIT Rate	Total
The Contractor shall refer to all drawings and tender documents, including the specifications, and shall comply with all requirements contained therein. This includes, but is not limited to, the satisfactory completion of the Works in accordance with the approval of NRC Engineer and all relevant statutory authorities, (SWC, WES) regardless of whether such requirements are explicitly stated in the Bill of Quantities.					
1	Excavation And Backfilling				
1.1	Excavation of (1-2) m depth trench for laying 4 inch HDPE pipes by mechanical / manual means in foundation trenches or drains (not exceeding .5 m in width this including re-backfilling with excavated material responsibly.	520	ML		
1.2	Excavation of (1-.5) m depth trench for laying 2 inch HDPE pipes by manual means in foundation trenches or drains (not exceeding .3 m in width this including re -backfilling with excavated material responsibly.	200	ML		
2	Enter Connection to Main Pipeline				
2.1	Excavations & Backfilling: Excavation for 4-inch polyethylene pipe from the existing 4 inch to the center of camp as an extension to insure the length is adequate to supply the 2 inch HDPE pipes , with a depth of (100-450) cm (depending on site conditions) and 30 cm in width. The price shall include a 10 cm bedding and backfilling with excavation residues, as per engineering specifications and to the satisfaction of the NRC technical guidelines	520	ML		
2.2	Excavations & Backfilling: Excavation for 4-inch polyethylene pipe from the existing 4 inch to the center of camp as an extension to insure the length is adequate to supply the 2 inch HDPE pipes , with a depth of (100-450) cm (depending on site conditions) and 30 cm in width. The price shall include a 10 cm bedding and backfilling with excavation residues, as per engineering specifications and to the satisfaction of the NRC technical guidelines	200	ML		
3	Accessories and connections				
3.1	Supply and install of 4-inch high-density polythene T (تي) including labour cost and connecting as per specifications and instructions	1	No		

3.2	Supply and install of 4-inch high-density English Valve (بلف انجليزي) including labour cost and connecting as per specifications and instructions	2	No		
3.3	Supply and install of 4-inch Flanged adapter (ادابير مع فلنشه) including labour cost and connecting as per specifications and instructions	6	No		
3.4	Supply and install of 4-inch high-density polythene Elbo (كوع) including labour cost and connecting as per specifications and instructions	1	No		
3.5	Supply and install of 4-inch high-density polythene (جلبة ضهر) Back sleeve r including labour cost and connecting as per specifications and instructions	2	No		
3.6	Supply and install of 4-inch *3 PPRC Gaffes (ففيس) including labour cost and connecting as per specifications and instructions	1.0	No		
4	Excavation and backfilling works				
4.1	Excavation : Excavations & Backfilling: Excavation under distribution point 3 * 2 , with a depth of 30 cm. The price shall include a 30 cm bedding and backfilling with Hmari backfilling material with compaction ratio 25%, as per engineering specifications and to the satisfaction of the NRC technical guidelines	21.0	M3		
5	Conceret works				
5.1	Plan concrete				
5.2	Supply materials, cast and construct (3*2 m) 15 cm thick plain concrete (Grade 20 N/mm ²) for Foundation; rate shall include, ready mix/ in-suite concrete, formwork, labour, sampling, testing, mix design, curing, ...etc.) according construction drawings, the Technical Specification to NRC satisfaction	5.9	M3		
6	Masonry works				
6.1	Masonry Work: Supply materials and construct a 20 cm w high, two-brick thick red brick surrounding wall on a plain concrete base, as per technical specifications and NRC Engineer's instructions.	6.2	M2		
7	Reinforced concrete				
7.1	Supply materials, cast and construct (2.2*2 m) 10cm thick reinforced concrete (Grade 35N/mm ²) for Foundation ; rate shall include reinforcement steel of T12@200mm C/C, ready mix/ in-suite concrete, formwork, labour, sampling, testing, mix design, curing, ...etc.) according construction drawings, the Technical Specification to NRC satisfaction	1.2	M3		
7.2	Supply materials, cast and construct (2.2*5 m) 12 cm thick reinforced concrete (Grade 35N/mm ²) for stand from the foundation end level ; rate shall include reinforcement steel of T12@200mm C/C double mish , ready mix/ in-suite concrete, formwork, labour, sampling, testing, mix design, curing, ...etc.) according construction drawings, the Technical Specification to NRC satisfaction	0.8	m3		
8	Drainage Manhole				
8.1	Supply material and Connect a Drange 2 inch PI pipe 5 meter lengt for Waste water discharge into existing tree or plants	7.0	Nu		
9	Fittings : Supply materials and install all related fittings includes all necessary costs (labour, transportation and installation . The				

	connection shall be tested for leakage, as per engineering specifications and to the satisfaction of the NRC.				
9.1	Supply and install of 4*2 inch steel Galvanize reducer (مخفض) including labour cost and connecting as per specifications and instructions	7.0	Nu		
9.2	Supply and install of Nipple 2 inch (نبل 2 بوصة) including labour cost and connecting as per specifications and instructions	21.0	Nu		
9.3	Union 2 inch	21.0	Nu		
9.4	Supply and install of 2-inch high-density English Valve (بلف انجليزي) including labour cost and connecting as per specifications and instructions	7.0	Nu		
9.5	T cross 2*3/4 (Inch)	70.0	Nu		
9.6	Supply and install of 2-inch high-density polythene Elbo (كوع) including labour cost and connecting as per specifications and instructions	14.0	Nu		
9.7	Supply and install of 2-inch high-density polythene (جلية) Back sleeve r including labour cost and connecting as per specifications and instructions	14.0	Nu		
9.8	"Supply and install of 3/4 inch taps galvanized (حنفية) including labour cost and connecting as per specifications and instructions"	70.0	Nu		
10	Finishing works :				
10.1	Plastering Work: Supply materials, cast, and apply a 20 mm thick cement/sand plaster layer in two coats (1:6 cement-sand mix), finished smooth on the brick walls constructed and casted reinforced concrete , as per technical specifications and to NRC Engineer satisfaction	48.1	M2		
10.2	Painting: Supply materials, mix, and apply two coats of emulsion paint on well-prepared plaster, with a primer lime coat and oil-based finish. Colours to be decided on-site. All works to be carried out as per technical specifications and to NRC Engineer satisfaction	48.1	M2		
	Total Amount			-	
	VAT				
	COLLECTION TOTAL TO SUMMARY WITH 17% VAT INCUDED			-	
	currency				

Location and scope pf work :

Location:

Guli locality (WD SHMAM - Altbrat - Awd Allah)- Kosti locality Goz alsalam IDP camp

Scope : . BoQ for Installation/ Rehabilitation 3 of Water Points & Donkey cart filling stand at Guli locality (WD SHMAM - Altbrat - Awd Allah)-Installation/ Rehabilitation 7 of Water Points with Pipeline Extension in goz alsalam IDPs camp

Selection Criteria :

Criteria	Benchmark	Scoring	Criteria Weight (%)
Price	Lowest bid	(Min offered price / bid price) × 35	35%
Payment Terms	• 30% Upon delivery of materials and equipment mobilization of 100% • 70% upon completion of 100% of the work	Acceptance	5%
	Financial Capacity (ban state for the past • Six month) =10		
Quality	2 Previous experiences in water supply projects / water Rehabilitation related contracts/ Pipeline connection COC or PO point per contract/COC The full mark is 25 pints		

	Geographic Area especially in White Nile 0= no experience 3= some experience in the region 5=experience work in White Nile with supporting document (Contract / Certificate of job completion / reference letter)		
Delivery Time	Benchmarked at Four weeks		20%

What is the currency of the quote? DO NOT PROVIDE QUOTES IN BOTH SDG AND USD CURRENCIES.	
Delivery Lead Time (in days, from receipt of NRC Purchase Order/sign contract)	
Bid Validity Period (in days from receipt of NRC Purchase Order):	
Please confirm the following payment terms: <u>100% After work completion</u> If not accepting above payment term, please specify	
Please provide a copy of the bank account statement or audited bank account statement	
Please provide any experience certificates, including relevant experience for water Pipeline work	

Name	
Position	
Date Signature Stamp	

RFQ Terms & Conditions

Manner of Submission:

- By hand in a sealed envelope to NRC Kosti Area Office located in **White Nile State, Kosti, Alandalus Area, Alandalus Street, North of WFP.**
- By email to the dedicated and secured email address: sd.procurementskao@nrc.no
-
- **(offers received on other email addresses will not be considered)** with subject: **PF-KSI-AO-805**
- Before the Closing date & Time mentioned above. Companies who do not submit their quotation by this deadline will not be considered.

Requirements:

- All Bids must include all customs and taxes payable in the country of delivery unless the RFQ specifically requests differently
- Bids must be submitted in the currency indicated in the RFQ. Bids in other currency might not be accepted
- Bids must be valid for the validity period indicated in the RFQ. Bids not meeting this validity period might be disqualified
- All enquires and questions should be addressed to the email given in the RFQ details section. All questions and answers will be shared with all invited suppliers.
- NRC reserves the right to accept or reject the whole or part of your quotation based on the information provided. Incomplete quotations which do not comply with our conditions will not be considered.

Assessment Criteria:

- All bids received and accepted will be evaluated based on the following:
- Step 1: Administrative compliance check: Each bid will be checked to ensure compliance with all the RFQ requirements
- Step 2: Technical Evaluation: All bids will be technically evaluated based on “best value for money”
- Step 3: Financial Evaluation: Price in comparison to NRC established expectation and in comparison, to other bidders of comparable technical quality

Mandatory documents:

Requested document	Check (Y/N)
Company registration Certificate	
Tax registration certificate	
NRC RFQ TO BE SIGNED AND STAMPED IN EACH PAGE	
Relevant experience certificate (if available)	

Payment terms:

- Payment will be made within **30 days** of receipt of goods, by bank transfer/cheque only.

NRC is obliged to ensure that its procurement decisions are clearly justified and documented and keeping within the Donors mandatory principles. In that regard, full and on-the-spot access must be granted to representatives of NRC, the Donor or any organisation or person mandated by it, to premises belonging to NRC or its contractors. The right to access shall include all documents and information necessary to assess or audit the implementation of the contract.

NRC also expects suppliers who process personal data to comply with the General Data Protection Regulation (EU GDPR) and any relevant national legislation. Suppliers processing personal data on an NRC contract will be required to sign a data processing / sharing agreement as part of the contract. Refusal to sign such an agreement constitutes refusal of the contract terms and forfeiture of the contract on the part of the supplier.

If the activities of the contract take place in areas with Explosive Hazards, NRC accepts no liability for injury and/or death to contractor's staff or damage to contractor's property.

Anti-money laundering, anti-bribery, anti-corruption and anti-terrorism legislation and donor regulations require NRC to screen contractors against various international lists to ensure due diligence. Submission of the quotation constitutes acceptance of these screening practices.

NRC aims to purchase products and services with minimum environmental impact. Environmental considerations form part of the NRC selection criteria, and NRC reserves the right to reject quotations provided by suppliers not meeting these standards.

All suppliers doing business with NRC should maintain high standards on ethical and environmental issues, respect and apply basic human and social rights, ensure non-exploitation of child labour, and give fair working conditions to their staff. **Suppliers will be required to sign and submit an Ethical Standards Declaration, together with their bid.**

NRC reserves the right to reject quotations provided by suppliers not meeting these standards.

