BOQ for the rehabilitation Sanitation Facilities in Al Bashagra hospital four VIP latrines

Date of BoQ 12/24/2025

HA - Sudan Al jazeera State office

#	Items	Unit	Quantity	Unit Cost (SDG)	Total Cost SDG
	Floor works				
1	Supply materials Ceramic tile 40 mm*40 mm frist class and cement, sand and carry out the floor installation and 1 m high surounding the interal wall	m²	96		
3	Provision and installation of marble seat (local marble seat) with pure flash and all juctions for disables for two stances.	PCs	18		
	Door and window				
4	Metallic latrine doors, 0.9m wide x 2.1m high and 1.5in thick using steel angles and iron plates, with 4" hinges, external and internal sliding locks including a padlock.	Door	16		
5	Metallic latrine window, 0.4m wide x 0.4m high using steel angles and iron plates net (X band), with 4" hinges and carry out the installation accordingly.	window	16		
	Plumbing				
6	Supply materials cement,sand and PPR ¾ inch pipe, fittings and sand and carryout the plumbing works and install ditribution system from elevated tank to four stances per latrine.	job	1		
7	Supply material PPR 1 inch pipe with nacessarly fitting and carry out the installation of conveyance system from elevated tak to storage tank and fix inlet and outlet	job	1		
8	Provide pure flish 10 liter capacity with all juntion and install it accordingly	PCs	16		
	Painting and finishing				
9	provide painting (UNICEF color) and carry out internal and external painting three code (white internally) and bule outside.	m²	200		
10	Install signboard with UNICEF, FCDO, Human Appeal and state ministy of health logos	PCs	2		
Total in Word SDG					-

Company/NGO/CBO Name:

Name of Director:

Signature and stamp

Date: