

Financial Offer

Requisition # 4330524

Drilling 3 Boreholes in Bau Locality – Medium, Melbel and Bofai- Blue Nile State.

Supplier Name: _____

Address: _____

Contact #: _____

Email: _____

Date: _____

BoQ

All specifications and attached with this tender

Fill out the table below:

BILLS OF QUANTITIES FOR BOREHOLE DRILLING					
Item	Description	Unit	Qty	Rate (USD)	Amount (USD)
	Bill No. 1 Preliminaries and General				
1	Mobilization and demobilization of sites	Ls	1		
2	Preparation and submission of 2 Completion Report and online PDF copy (With photographs, Community signed certificate including GPS Coordinates)	Ls	1		
	Bill No 2: Preparatory activities for drilling works				
3	Drilling of boreholes 12¼" diameter to Hardrock or maximum depth of 40 m including all equipment, test drilling, material and personnel needed for the drilling process.	m	20		
4	Drilling of boreholes 8½" diameter in hard rock or maximum depth of 40 m including all equipment, test drilling, material and personnel needed for the drilling process.	m	50		
5	Sampling and storage of drill cutting every 3 m	Ls	1		
6	Borehole development (airlift/compressor) until: • The discharged water is clear. • Sand content is within acceptable limits.	Ls	1		
	Bill No 3: Supply and installation of casing and grouting Casing				
7	Supply and installation of 6" uPVC plain casing, PN 10	m	61		
8	Supply and installation of 6" uPVC screen, PN 10, slot width 1,0 mm	m	9		
	<i>Grouting and Cementing</i>				
9	Supply and placement of gravel pack of gravel size as per specification	m	40		
10	Supply and placement of sanitary seal of approved material or as per specification	m	3		
	Bill No 4: Pumping Test & Signpost				

11	Setting up and dismantling of the pumping test unit, pump rate approximately up to 30m ³ /h, pressure head of approximately 150 m	Ls	1		
12	Conducting pumping test - Step Test Pumping time	Hr.	2		
13	Conducting pumping test - Constant Rate Pumping time (<i>provisional</i>). Acceptable minimum yield shall not be less than 10,000 liters/hr.	Hr.	24		
14	Conducting pumping test - Recovery time	hr.	2		
15	Conduct joint water sampling and water quality testing through an approved national water quality laboratory.	Item	1		
16	Supply and fix donor signpost (Size 1.5m x 2.5m) as Per Project Manager recommendation and Guidance	Item	1		
Item	Description of bills brought to summary				Amount (USD)
1	Preliminaries and General				
2	Preparatory activities for drilling works				
3	Supply and installation of casing, grouting				
4	Pumping Test				
	Total for 1 borehole drilling 17% VAT Inclusive				
Total for 3 boreholes drilling 17% VAT Inclusive					
VAT 17%					
Grand Total					

Total in words: (.....)

Currency

Offer Validity (days)

Delivery Time:

Delivery location:

Payment terms:

Name: _____

Signature: _____

Stamp

Note: Please attached the Performa Invoice